

ABSTRACT

Hanni Siti Zahwa, 12319738

Infrastructure Development Project for Biodiversity Green House Facility (package 4) LIPI Cibinong

Department of Civil Engineering.

Faculty of Civil Engineering and Planning.

Gunadarma University.

(XIII + 49 + Attachment)

The LIPI Cibinong Green House Biodiversity Facility Infrastructure Development Project (package 4) is located in the Cibinong Science Center And Garden (CSC-BG-LIPI) area. Jl. Raya Bogor Km. 46 Cibinong–Kabupaten. Bogor, West Java. The LIPI Green House Biodiversity Facility Infrastructure Development Project (package 4) is a project that is being undertaken by the Indonesian Institute of Sciences as the project owner and PT. ADHI KARYA (Persero) Tbk. as the main contractor. This building has a land area of 10,000 m² and a building area of 6400 m². With a contract value of Rp. 165,741,308,771. Jogging track is a track for running or jogging, jogging it self is the activity of walking fast or jogging so that the heart absorbs more oxygen so that the heart can be trained to work faster than usual. The work methods for making jogging tracks include preparatory work, road formwork installation work, plastic installation, wiremesh installation, dowel installation, cleaning, casting work, troweling work, grooving work, cutting work. The required casting volume for the jogging track is 37,379 m³.

Keywords : Working Method, Jogging Track, Working Volume.