

## **ABSTRACT**

Ayunda Airina, 10320064

*Project Pavement Reconstruction And Road Markings On The Jakarta Bogor – Ciawi Toll Road Section 2023.*

*Case Study: Methods For Implementing Rigid Pavement Work At The Gunung Putri Toll Gate (Entrance).*

*Civil Engineering Department. Faculty Of Civil Engineering And Planning.  
Gunadarma University.*

*(XVII+77+Appendix)*

*The Pavement Reconstruction and Road Markings Project on the Jakarta Bogor – Ciawi 2023 Toll Road Section is being carried out at several points along the Jakarta, Bogor, Ciawi (Jagorawi) toll road section. The Pavement Reconstruction and Road Marking Project on the Jakarta Bogor – Ciawi 2023 Toll Road Section is being managed by PT. Jasa Marga Tollroad Maintenance as the owner, PT. Eskapindo Matra, as a supervision consultant and KSO PT. Puja Persaka – PT. KADI International, as the main contractor. The type of contract used in the project is the Unit Fix Price with a contract value of Rp. 40,884,349,170.00 and work is carried out for 240 calendar days (8 months). Observations made by the Rigid Pavement Work Implementation Method at the Gunung Putri Toll Gate (Entrance) began with preparatory work, earthworks, sub drain work, foundation layer work, rigid pavement work and finishing work.*

*Keywords: Rigid Pavement, Implementation Method, Pavement*